



VILLAGE PLAN  
AREA 1

June 22, 2017

FINAL



WILDFLOWER

AT SARATOGA SPRINGS

---

A **DAI** Community



# VILLAGE PLAN

## Prepared By:

---

DAI

Landmark Design

LEI

Hales Engineering

# Table of Contents

SECTION 1: Legal Description .....	S 1 - 1
SECTION 2: Detailed Use Map.....	S 2 - 1
SECTION 2 (cont'd): Detailed Use Map.....	S 2 - 2
SECTION 3: Detailed Buildout Allocation .....	S 3 - 1
SECTION 4: Development Standards.....	S 4 - 1
SECTION 5: Design Guidelines.....	S 5 - 1
SECTION 5a: Fencing Plan.....	S 5 - 15
SECTION 6: Associations.....	S 6 - 1
SECTION 7: Phasing & Maintenance Plan.....	S 7 - 1
SECTION 7a: Phasing Plan .....	S 7 - 2
SECTION 8: Lotting Map .....	S 8 - 1
SECTION 9: Landscape Plan & Plant Palette .....	S 9 - 1
SECTION 10: Utility Plans.....	S 10 - 5
SECTION 10a: Culinary Water Plan.....	S 10 - 6
SECTION 10b: Secondary Water Plan.....	S 10 - 7
SECTION 10c: Sewer Plan.....	S 10 - 9
SECTION 10d: Storm Water Drainage Plan .....	S 10 - 10
SECTION 10e: Capital Facility Upgrade Plan.....	S 10 - 11
SECTION 11: Vehicular Plan .....	S 11 - 1
SECTION 12: Pedestrian & Bicycle Plan.....	S 12 - 1
SECTION 13: Density Transfers.....	S 13 - 1
SECTION 14: Additional Detailed Plans .....	S 14 - 1
SECTION 14a: Neighborhood Names.....	S 14 - 2
SECTION 14b: Signage Plan .....	S 14 - 3
SECTION 14c: Grading Plan.....	S 14 - 7
SECTION 14d: Open Space Management Plan .....	S 14 - 8
SECTION 14e: Natural Resources Inventory Plan .....	S 14 - 26
SECTION 14f: Wildlife Mitigation Plan.....	S 14 - 27
SECTION 14g: Sensitive Lands Protection .....	S 14 - 28
SECTION 14h: Fire Protection Plan .....	S 14 - 29
SECTION 14i: Traffic Study.....	S 14 - 30
SECTION 14i: Traffic Study (cont'd) .....	S 14 - 31
SECTION 15: Site Characteristics.....	S 15 - 1
SECTION 16: Findings .....	S 16 - 1
SECTION 17: Mitigation Plans.....	S 17 - 1
SECTION 18: Offsite Utilities.....	S 18 - 1
SECTION 19: Master Development Agreement.....	S 19 - 1



# SECTION 1: Legal Description



ENGINEERS  
SURVEYORS  
PLANNERS

## LEGAL DESCRIPTION PREPARED FOR DAI Job No. 13-0902 (April 27, 2016)

### VILLAGE PLAN LEGAL DESCRIPTION

A Portion of the West Half of Section 10 and the South Half of Section 3, Township 5 South, Range 1 West, Salt Lake Base and Meridian, described as follows:

Beginning at the North 1/4 Corner of Section 10, Township 5 South, Range 1 West, Salt Lake Base and Meridian; thence  $S0^{\circ}11'02''W$  along the Quarter Section Line 3688.23 feet; thence  $N89^{\circ}48'58''W$  491.89 feet; thence  $N15^{\circ}21'47''W$  459.85 feet; thence along the arc of a 4440.00 foot radius curve to the right 2668.32 feet through a central angle of  $34^{\circ}26'00''$  (chord:  $N1^{\circ}51'13''E$  2628.34 feet); thence  $N19^{\circ}04'13''E$  684.52 feet to the southerly line of that real property described in Deed Entry No. 3238:2014 in the official records of the Utah County Recorder; thence along said real property the following six (6) courses:  $S18^{\circ}26'38''E$  1.65 feet; thence  $S25^{\circ}22'31''E$  60.27 feet; thence  $N89^{\circ}45'50''E$  164.03 feet; thence  $N0^{\circ}02'37''E$  198.17 feet; thence  $S89^{\circ}57'58''W$  121.39 feet; thence  $S64^{\circ}33'09''W$  20.59 feet to the proposed easterly right-of-way line of Mountain View Corridor; thence along said right-of-way line the following eight (8) courses: along the arc of a 3000.00 foot radius non-tangent curve to the right (radius bears:  $S67^{\circ}52'05''E$ ) 409.38 feet through a central angle of  $7^{\circ}49'07''$  (chord:  $N26^{\circ}02'28''E$  409.06 feet); thence along the arc of a 8140.00 foot radius curve to the left 1433.58 feet through a central angle of  $10^{\circ}05'27''$  (chord:  $N24^{\circ}54'18''E$  1431.73 feet); thence along the arc of a 750.00 foot radius curve to the right 974.95 feet through a central angle of  $74^{\circ}28'49''$  (chord:  $N57^{\circ}06'00''E$  907.74 feet); thence  $S85^{\circ}39'35''E$  665.49 feet; thence along the arc of a 1500.00 foot radius curve to the left 438.11 feet through a central angle of  $16^{\circ}44'05''$  (chord:  $N85^{\circ}58'22''E$  436.56 feet); thence  $N77^{\circ}36'20''E$  298.85 feet to the East Line of Section 3, Township 5 South, Range 1 West, Salt Lake Base and Meridian; thence  $S0^{\circ}05'10''E$  along the Section Line 1023.87 feet; thence  $N89^{\circ}51'58''E$  547.97 feet to the East Bank of the Jacob Welby Canal; thence along the said East Bank the following six (6) courses:  $S16^{\circ}33'17''E$  43.07 feet; thence  $S9^{\circ}58'30''E$  53.91 feet; thence  $S6^{\circ}37'28''W$  103.89 feet; thence  $S9^{\circ}27'03''W$  107.43 feet; thence  $S8^{\circ}32'21''W$  53.31 feet; thence  $S6^{\circ}29'17''W$  48.17 feet; thence  $N89^{\circ}58'51''W$  1118.84 feet to the Northwest Corner of Plat "W", Harvest Hills Subdivision; thence  $S26^{\circ}33'37''W$  along the westerly line of Plats "W & R/S", Harvest Hills Subdivisions 1040.70 feet; thence  $S89^{\circ}36'29''W$  along Plats "Z, AA & CC" Harvest Hills Subdivisions 1346.34 feet; thence  $N9^{\circ}35'01''E$  216.50 feet; thence West 315.47 feet; thence  $S3^{\circ}19'17''E$  215.67 feet to the point of beginning.

Contains: ±168.69 Acres

- Civil Engineering
- Structural Engineering
- Surveying
- Land Planning
- Landscape Architecture

[www.lei-eng.com](http://www.lei-eng.com)


Note: Acreage in legal description varies from Community Plan. See exhibit on page S1-2.

Corporate Office: 3302 N. Main Street • Spanish Fork, UT 84660  
Salt Lake Office: 14441 South 980 West • Bluffdale, UT 84065  
Boise Office: 2040 S. Eagle Road • Meridian, ID 83642

☎ 801.798.0555    📠 801.798.9393  
☎ 801.495.2844    📠 801.495.2847  
☎ 208.846.9600




Note: Acreage in legal description varies from Community Plan.







# SECTION 2 (cont'd): Detailed Use Map





## SECTION 3: Detailed Buildout Allocation

The following information details the allocation of all acreage within Village Plan Area 1 (Refer to Phasing and Maintenance Plan in Section 7).

Area	Land Use	Acres	ERUs Assigned in the Community Plan	ERUs in Village Plan Area 1	Percent Change	ERUs/Gross Acre
Neighborhood 1	Single Family Residential	19.33	79	80	+1.0%	2.64
	Open Space	5.03				
	ROW	5.85				
Neighborhood 2	Single Family Residential	13.24	51	51	0%	2.84
	Open Space	0.68				
	ROW	4.03				
Neighborhood 3	Single Family Residential	19.93	128	125	-2.4%	4.44
	Open Space	1.67				
	ROW	6.56				
Neighborhood 4	Single Family Residential	17.55	109	94 (2 of these for the church)	-12.8%	2.71
	Open Space	6.39				
	Church	3.76				
	ROW	7.39				
Neighborhood 5	Single Family Residential	10.58	55	47	-14.6%	2.32
	Open Space	0.15				
	ROW	9.92				
Neighborhood 6	Single Family Residential	22.43	128	138	+7.8%	4.66
	ROW	7.16				
Neighborhood 7	Single Family Residential	5.71	30	36	+1.2%	3.77
	Open Space	1.82				
	ROW	2.01				
Village Plan Area 1	Master Planned Roads	4.57	N/A	N/A	N/A	N/A
Total ERUs Village Plan Area 1			580	571	-2.1%	

Note: See Lotting Plan for Neighborhood Breakdown in Section 8.

### Future Population Projections

According to the City's Parks, Recreation, Trails, and Open Space Master Plan (2011), the average household size in Saratoga Springs is 4.05 persons. The total number of new housing units in Village Plan Area 1 is 571. Multiplying the number of new housing units by the average household size of 4.05 persons provides a future population projection of 2,316.6 for Village Plan Area 1.

### Employment Levels

The land uses within Village Plan Area 1 are single family residential, open space, church, and right-of-way; therefore no employment will be provided in Village Plan Area 1.



# SECTION 4: Development Standards

## Building Form — Single Family Residential

Disclaimer: If any requirements in the Development Standards conflict with City or State Codes, the City or State codes take precedence over the Development Standards.

BUILDING CONFIGURATION	
Number of Bldgs. per Lot	1 + outbuilding
Height — Principal Building	35' maximum height measured at vertical distance from established finished grade surface at the building wall to the mean highest level between eaves and ridge for gable, hip, or gambrel roofs.
Height — Outbuilding	Equal to or less than 20 feet
Lot Coverage	50% maximum
Lot Frontage	45' minimum measured at front setback
Lot Size	Varies by neighborhood (see S8-1). Minimum lot size on corner lots shall be increased by 10%
SETBACKS — SINGLE FAMILY DWELLINGS	
Front Yard*	15' minimum
Front Access Garage	20' minimum (to garage)
Side Access Garage	24' minimum (subject to standard driveway approach widths)
Rear Yard	10' minimum
Side Yard*	Varies by lot size measured at front setback (see Section 8-1)
Corner Front Yard	15' minimum
Corner Front & Side Access Garages	20' minimum
Corner Side Yard Facing Street	15' minimum
SETBACKS — ACCESSORY STRUCTURES REQUIRING A BUILDING PERMIT	
Front Yard	Same as principal building
Side Yard	5' minimum
Rear Yard	5' minimum

\* All subdivisions in Wildflower Village Plan 1 that utilize a 15' front setback shall be required to include a note placed on the plat as notification that proper buffering shall be required to meet Questar Gas Standards. Failure to meet proper buffering between the private utilities and public right-of-way may result in additional setback requirements and/or removal of foundations to meet this requirement.




# SECTION 4: Development Standards (cont'd)

## Building Form — Single Family Residential

Neighborhood 1 - Primrose



Building Setback Detail




# SECTION 4: Development Standards (cont'd)

## Building Form — Single Family Residential

### Neighborhood 2 - Primrose



### Building Setback Detail




# SECTION 4: Development Standards (cont'd)

## Building Form — Single Family Residential

### Neighborhood 3 - Sego Lily




### Building Setback Detail




# SECTION 4: Development Standards (cont'd)

## Building Form — Single Family Residential

### Neighborhood 4 - Sego Lily




### Building Setback Detail



# SECTION 4: Development Standards (cont'd)


## Building Form — Single Family Residential

### Neighborhood 5 - Daisy



Note: The landscaped island and parking area associated with it are subject to change or deletion.


### Building Setback Detail




# SECTION 4: Development Standards (cont'd)

## Building Form — Single Family Residential

Neighborhood 6 - Daisy




Building Setback Detail




# SECTION 4: Development Standards (cont'd)

## Building Form — Single Family Residential

### Neighborhood 7 - Wild Rose




### Building Setback Detail



# SECTION 4: Development Standards (cont'd)

## Private Open Space — Single Family Residential



\* Lawn, patio, and garden areas are subject to approval by the Wildflower Design Review Committee (WDRC).

PRIVATE YARD*	
Permitted Elements	Front Yard: Fences, hedges, & masonry walls (4' max. height/3' max. height inside clear-view triangle). Rear & Side Yard: 6' fences.
Surface Treatments	Groundcover, lawn, trees, flower gardens, vegetable gardens, & small shrubs. Stone mulch limited use with approval of WDRC. Landscape boulders are allowed. Artificial turf not allowed in front yard.
Decks	Decks may not extend into setback. Deck must stay within the setbacks as described above.
Schedule	All residential lots in single family areas shall have the front yard and side yards landscaped within one year, and interior side and back yards within two years after receiving a certificate of occupancy. Please reference City Code "Section 19.06.05 Completion of Landscape Improvements; Adequate Assurances" for exceptions to this requirement due to weather conditions.

## Parking — Single Family Residential

Two off-street parking spaces are required per single family residential unit. Driveways for single family residential units meet this requirement. Please reference City Code "Section 19.12.06 General Subdivision Improvement Requirements" for standards on garages and covered parking.

## Subdivision Access — Single Family Residential

Two separate means of vehicular access onto a collector or arterial road shall be required whenever the total number of dwelling units exceeds fifty. Please reference "Section 19.12.06 General Subdivision Improvement Requirements" for standards on placement and exceptions to this requirement.



# SECTION 5: Design Guidelines

## Architecture Materials

The architectural standards presented in this Village Plan document are meant to govern the selection of building material and color scheme. The matrix below contains the potential building materials and how they can be used on the included home elevations. Materials are not limited to the details below. Additional materials may be introduced once approved by the WDRC. New materials to be introduced must maintain a high level of quality similar to the products listed below, and must be shown to be appropriate to a specified architectural style.

		ARCHITECTURAL STYLES				
		Prairie	Craftsman	Farmhouse	Utah Traditional	European
EXTERIOR MATERIALS	Composite Siding	*	*	*	*	*
	Stone / Brick	*	*	*	*	*
	Stone / Brick Not Required*	*	*	*		
	Stucco	*	*	*	*	*
	Architectural Asphalt Shingles	*	*	*	*	*
	Gable Returns				*	*
	Metal Roofing	*	*	*		
	Main Body Low Pitched Roofs (Under 6/12—18" Minimum Overhang)	*	*	*		
	Exposed Rafter Tails	*	*	*		*
	Shutters	*		*	*	*
	Arched Windows				*	*




# SECTION 5: Design Guidelines (cont'd)

## Craftsman Elevation

---

The Craftsman Style originated in Southern California and quickly became the dominant style for smaller homes built throughout the country in the early 1900s. Though bungalows are the most common form of the Craftsman elevation, “high-style” interpretations can be found in various locations and are sometimes called “stick houses.” The following features identify a Craftsman style home:

- » Lap siding, board and batten, and shake and shingle exteriors with limited use of stucco
- » Low-pitched gable roofs (4/12 and 6/12 roof pitches are most common)
- » Exposed rafter tails under eaves
- » Decorative corbels and braces
- » Front porches with possible extensions to the side and rear of the home
- » Porch supports (columns/pillars) that are typically rectangular or tapered (not round) with masonry bases. All columns/pillars to be a minimum of 12 inches square.
- » Large roof overhangs (typically 18 to 24 inches wide)
- » Window grids
- » Heavy, thick fascia
- » Single-hung and double casement windows
- » Exposed, decorative beams
- » Garage windows



Window and Door  
Casing and Trim





# SECTION 5: Design Guidelines (cont'd)

## Farmhouse Elevation

---

The design of the American Farmhouse was initially influenced strictly by function and geography. The farmhouse was always unpretentious, straightforward, and functional. It was shaped by the needs of the farmers, the local climate, and the materials available. The original farmhouse represented simple shelter structures, yet provided a place of pride to entertain important relatives and live their lives in some comfort. Today, there is a growing interest in a simple, back-to-basics lifestyle. The American Farmhouse symbolizes that ideal, and it gives today's homeowners a tangible and sentimental connection to the nation's history. The following features identify a Farmhouse style home:

- » Simple, single or double column porch supports (columns/pillars)
- » Simple, rectangular floor plan
- » Dormers
- » Large, and often wrap-around, porches
- » Window grids
- » Large flat surfaces of board and batten on front elevation (typically 1.5 to 2 stories tall)
- » Low roof pitches above porches (typically 3/12 to 5/12)
- » Steeper roof pitches recommended on all other roofs, often as steep as 10/12 to 12/12
- » Gable-style roofs (not hipped)
- » Dormers (gabled and shed dormers are appropriate)
- » Taller, more narrow windows
- » White or light-colored exterior colors (strongly recommended)
- » Dark or colored windows are common





Farmhouse Examples



# SECTION 5: Design Guidelines (cont'd)

## European Elevation

---

The Wildflower European style combines an old world and romantic charm with modern elements. This style of home showcases many European influences such as Italian influence, Tudor style design cues, Mediterranean floor plans and Spanish home designs; the European style can easily range in size to fit each individual family's needs. These homes are characterized by medium to steep roof pitches, detailed entrances, hip roof forms, arched openings and shutters. Unique elements such as multi-paneled windows of varying sizes, spacious living areas and high ceilings create the unique blend of comfort and refinement. The following features identify a European style home:

- » Moderate to high roof pitches
- » Hip roof forms
- » Arched or square openings
- » Decorative front porches
- » Shutters





European Examples



# SECTION 5: Design Guidelines (cont'd)

## Prairie Elevation

---

The Prairie elevation is a recent style created by incorporating modern elements into the style of a traditional prairie home. This design emphasizes the simplicity and integrity that combines comfort, utility, and beauty, without imitating past styles. Prairie home plans have broad, gently sloping, shelter roofs with prominent, low chimneys. Balconies and terraces extend in several directions beyond the basic house, creating a protected outdoor space and a rhythm of vertical and horizontal planes. The following features identify a Prairie style home:

- » Low roof pitches (4/12-6/12)
- » Large modern-style windows (typically without grids)
- » Overhanging eaves, 18" to 24" recommended (Note: Eaves must be fire rated if less than 5 feet from property line)
- » Horizontal, clean lines in the detailing
- » Lap siding or stucco with masonry details
- » Open floor plans
- » Wide, rectangular columns/pillars
- » Prominent low chimneys
- » Brick as needed for masonry elements

**The following features are often incorporated into traditional Prairie style homes in order to add a contemporary feel:**

---

- » Large, tall windows
- » Modern, glass panel front door and garage
- » Wide front door (42 inches wide or larger)





Prairie Examples



# SECTION 5: Design Guidelines (cont'd)

## Utah Traditional Elevation

---

Traditional Utah architecture is very similar to domestic architecture elsewhere in the United States. This style is based on existing cultural traditions and/or current trends in architecture, rather than being original. It does, however, represent the early pioneer heritage and the eventual merging of Utah with mainstream American society. The result provides a certain sameness from community to community. The following features identify a Utah Traditional home:

- » Roof pitches (6/12 and greater)
- » Hipped and gabled roofs are common
- » Shutters
- » Masonry (brick or stone)
- » Body materials of siding or stucco
- » Gable returns
- » Arched windows, front doors, and garages
- » Use of copper or other metal on small roof elements
- » Bay or boxed windows
- » Wide front door (42 inches wide or larger)





Utah Traditional Examples



# SECTION 5: Design Guidelines (cont'd)

## Exterior Color Schemes

All exterior colors will be compatible with the architectural style of each dwelling. Bright artificial colors such as pastels, neons, fluorescents, etc will not be allowed.


Color is a critical element for creating the ambiance of the overall community. A well-designed color palette should be based on natural elements. Appropriate use of color will bring unity to each neighborhood and help establish a sense of community. Additional colors may be added upon approval by the WDRC.



EXAMPLE COLORS - 01



Front Door  
Manufacturer:  
Kwal  
Color:  
Racoon CL3176N



Soffit, Fascia, Trim  
Manufacturer:  
Hardie Color Plus  
Color:  
Arctic White




Hardie - Color 1  
Manufacturer:  
Hardie Color Plus  
Color:  
Boothbay Blue



Hardie - Color 2  
Manufacturer:  
Hardie Color Plus  
Color:  
Sandstone Beige

EXAMPLE COLORS - 02



Front Door  
Manufacturer:  
Kwal  
Color:  
Jumpsuit CL2986A



Soffit, Fascia, Trim  
Manufacturer:  
Hardie Color Plus  
Color:  
Arctic White




Hardie - Color 1  
Manufacturer:  
Hardie Color Plus  
Color:  
Heathered Moss




Hardie - Color 2  
Manufacturer:  
Hardie Color Plus  
Color:  
Sandstone Beige

EXAMPLE COLORS - 03



Front Door  
Manufacturer:  
Sherwin Williams  
Color:  
Fireweed SW6328



Soffit, Fascia, Trim  
Manufacturer:  
Hardie Color Plus  
Color:  
Arctic White



Hardie - Color 1  
Manufacturer:  
Hardie Color Plus  
Color:  
Timber Bark



Hardie - Color 2  
Manufacturer:  
Hardie Color Plus  
Color:  
Sandstone Beige



### **Native Regional Suitability**

The color palette established for Wildflower has been based on the native flowers found at Wildflower and the surrounding area as well as a variety of hues found in the landscape. Approved colors include native and natural tones found in the Utah landscape, including earth tones and colors indicative of mountainous and prairie settlements.

### **Stylistic Appropriateness**

The colors used at Wildflower should reflect the architectural styles being offered at Wildflower. Fewer colors are typically more appropriate than incorporating a large variety of colors on individual buildings. This keeps homes from distracting from the overall ambiance of the community.

### **Community Cohesiveness**

The relationship of colors between neighboring homes is critical when selecting the palette for each building facade. A sense of flow is created by balancing building elements, which have similar tones across many buildings, yet incorporate a variety of color elements, making each home unique.

### **Main Body and Trim**

Color schemes for Wildflower may have a softer contrast between the main body and trim colors for a more subtle appearance. Alternatively, some homes may have a stronger contrast between the main body and trim colors.

### **Roofing Colors and Materials**


It is especially important to consider color variation with roofing materials in order to encourage diversity and architectural interest in each neighborhood and throughout the community.

### **Architectural Diversity**

To ensure the desired theme and architectural character for Wildflower is realized, and to ensure the Community is enriched by variety in its architecture, careful attention will be paid to the mix of homes within each neighborhood. The following guidelines shall be followed for the production of single-family homes, or where individual floor plans are offered on a repeating basis within a parcel or plat:




# Limitation on Repetition of Design and Color





# SECTION 5a: Fencing Plan



-  **REQUIRED: 6' VINYL SEMI-PRIVACY FENCE**
-  **REQUIRED: 6' VINYL PRIVACY FENCE**
-  **REQUIRED: 6' SIMTEK PRIVACY FENCE**
-  **OPTIONAL: 6' VINYL FENCE**

\* Required fences adjacent to lots are a requirement of the builder, not developer, and shall be installed prior to receiving certificate of occupancy.  
 \*\* If certificate of occupancy is issued between November and March, fencing to be installed by end of June.



# SECTION 5: Design Guidelines (cont'd)

## Fence Type Examples

---

**6' Vinyl Semi-Privacy Fence\***



**6' Vinyl Privacy Fence**



**6' SimTek Privacy Fence**



\*Openings in semi-privacy fence to match the City standard of 1-inch.



# SECTION 6: Associations

## Home Owners Associations

---

In accordance with section 19.26.03,2,d of the Planned Community Zone ordinance, a Master Home Owners Association (HOA) will be established to review, approve, and enforce architectural requirements and restrictions, and to address common area maintenance obligations for the entire Wildflower Community. Where required, typically in multi-family areas in later phases, sub-HOAs will be established to address area-specific costs.

## Wildflower Design Review Committee (WDRC)

---

In order to create, maintain and improve the Project as a pleasant, desirable and sustainable community, and to establish and implement a consistent and harmonious design concept and to protect and promote the present and future values of Wildflower Development, all exterior, architectural building elevations and building materials, colors and usage design, site plan and landscape treatments, wall and fencing, and signage within Village Plan Area 1 shall be subject to a Design Review Process and approval by the established Wildflower Development Review Committee (WDRC).

The WDRC shall review and approve all residential site plans and building permits prior to beginning the City of Saratoga Springs submittal and review processes. The WDRC shall consist of representatives from the following: the Master Developer and a selected team of design professionals, i.e. planners, engineers, architects, contractors, etc. The Master Developer shall retain the right to retain or replace members of the WDRC at its discretion.



# SECTION 7: Phasing & Maintenance Plan

## Phasing

---

As indicated on page 15 in the Wildflower Community Plan, Wildflower Village Plan Area 1 is the first phase for the Wildflower at Saratoga Springs development. Preliminary phasing for Village Plan Area 1 is shown on the Phase Plan on the following page, including open space. Phasing for open space in future village plan areas shown in the Detailed Use Plan in Section 3 will be determined at the corresponding Village Plan stage.

## Maintenance

---

Maintenance for all common open space areas within Wildflower Village Plan Area 1, including park strips, private parks, and developed and natural open space, will be provided by the Master Homeowners Association (HOA) described in Section 6 of this Village Plan. Any open space where ownership is transferred to the City for use as a City Park will be maintained by the City of Saratoga Springs.






# SECTION 7a: Phasing Plan


The balance of the open space approved in the plan is owned and controlled by UDOT, so improvement and use will correlate with their timeline.

Phases that depend on future improvements are not allowed.



WILDFLOWER  
AT SARATOGA SPRINGS

- NOTES:
- AREAS MAY BE MODIFIED OR BUILT OUT OF ORDER BASED ON AVAILABILITY AND EFFICIENCY OF UTILITIES AND MARKET CONDITIONS.
  - PHASES THAT DEPEND ON FUTURE IMPROVEMENTS ARE NOT ALLOWED.



RESIDENTIAL LEGEND										
AREA #	NEIGHBORHOOD	AREA	# OF LOTS	LOT AREA	RIGHT-OF-WAY AREA	CIVIC	OPEN SPACE AREA	RUNNING TOTAL AREA	RUNNING TOTAL OPEN SPACE	RUNNING TOTAL REQ. OPEN SPACE (23.92%)*
AREA #1	NEIGHBORHOOD #4	5.13 AC	--	--	1.37 AC	3.76 AC	--	5.13 AC	00 AC (0%)	1.23 AC
AREA #2	NEIGHBORHOOD #1	4.56 AC	--	--	--	--	4.56 AC	9.69 AC	4.56 AC (47.06%)	2.32 AC
AREA #3	MASTER PLANNED ROAD	0.93 AC	--	--	0.93 AC	--	--	10.62 AC	4.56 AC (42.94%)	2.54 AC
AREA #4	NEIGHBORHOOD #7	9.54 AC	36 LOTS	5.71 AC	2.01 AC	--	1.82 AC	20.16 AC	6.38 AC (31.65%)	4.82 AC
AREA #5	NEIGHBORHOOD #6	5.69 AC	26 LOTS	4.12 AC	1.57 AC	--	--	25.85 AC	6.38 AC (24.68%)	6.18 AC
AREA #6	NEIGHBORHOOD #1	13.19 AC	45 LOTS	9.64 AC	3.55 AC	--	--	39.03 AC	6.38 AC (16.35%)	9.34 AC
AREA #7	MASTER PLANNED ROAD	3.32 AC	--	--	3.32 AC	--	--	42.35 AC	6.38 AC (15.07%)	10.13 AC
AREA #8	NEIGHBORHOOD #3	7.86 AC	29 LOTS	5.25 AC	2.12 AC	--	0.49 AC	50.21 AC	6.87 AC (13.68%)	12.01 AC
AREA #9	NEIGHBORHOOD #2	17.95 AC	51 LOTS	13.24 AC	4.03 AC	--	0.68 AC	68.16 AC	7.55 AC (11.08%)	16.30 AC
AREA #10	NEIGHBORHOOD #4	11.78 AC	45 LOTS	8.89 AC	2.74 AC	--	0.15 AC	79.94 AC	7.70 AC (9.63%)	19.12 AC
AREA #11	NEIGHBORHOOD #3	11.42 AC	46 LOTS	7.76 AC	2.48 AC	--	1.18 AC	91.36 AC	8.88 AC (9.72%)	21.85 AC
AREA #12	NEIGHBORHOOD #4	7.25 AC	--	--	1.01 AC	--	6.24 AC	98.61 AC	15.12 AC (15.33%)	23.59 AC
AREA #13a	NEIGHBORHOOD #5	8.86 AC	30 LOTS	6.02 AC	2.86 AC	--	--	107.29 AC	15.12 AC (14.09%)	25.86 AC
AREA #13b	NEIGHBORHOOD #6	7.26 AC	34 LOTS	5.69 AC	1.57 AC	--	--	114.55 AC	15.12 AC (13.20%)	27.40 AC
AREA #14	NEIGHBORHOOD #3	8.86 AC	50 LOTS	6.92 AC	1.96 AC	--	--	123.43 AC	15.12 AC (12.25%)	29.52 AC
AREA #15	NEIGHBORHOOD #1	11.98 AC	35 LOTS	9.23 AC	2.28 AC	--	0.47 AC	135.43 AC	15.59 AC (11.51%)	32.40 AC
AREA #16	NEIGHBORHOOD #6	5.89 AC	24 LOTS	4.43 AC	1.26 AC	--	--	141.12 AC	15.59 AC (11.05%)	33.76 AC
AREA #17	NEIGHBORHOOD #4	10.93 AC	47 LOTS	8.66 AC	2.27 AC	--	--	152.05 AC	15.59 AC (10.25%)	36.37 AC
AREA #18a	NEIGHBORHOOD #5	1.80 AC	6 LOTS	1.54 AC	0.26 AC	--	--	153.85 AC	15.59 AC (10.13%)	36.80 AC
AREA #18b	NEIGHBORHOOD #6	10.97 AC	54 LOTS	8.22 AC	2.75 AC	--	--	164.82 AC	15.59 AC (9.46%)	39.42 AC
AREA #19	NEIGHBORHOOD #5	3.87 AC	11 LOTS	3.02 AC	0.70 AC	--	0.15 AC	168.69 AC	15.74 AC (9.33%)	40.35 AC
<b>TOTAL</b>		<b>168.69 AC</b>	<b>569 LOTS</b>	<b>108.77 AC</b>	<b>40.84 AC</b>	<b>3.76 AC</b>	<b>15.74 AC</b>	<b>168.69 AC</b>	<b>15.74 AC (9.33%)</b>	<b>40.35 AC</b>


\* PERCENTAGE BASED ON 23.92% OPEN SPACE REQUIRED ON DEVELOPER CONTROLLED PROPERTY, SEE OPEN SPACE PLAN.

**DAI**  
 1099 W. SOUTH JORDAN PARKWAY  
 SOUTH JORDAN, UT 84095  
 (801) 495-3414





# SECTION 8: Lotting Map



AREA	NEIGHBORHOOD LOT SIZE PERCENTAGE EXCEPTIONS	MIN. LOT SIZE WIDTH AT FRONT SETBACK	TYPICAL RANGE OF LOT SIZES	SIDE YARD SETBACKS
Neighborhood 1: Primrose*	N/A	60'	8,000 - 14,000	6'/12'
Neighborhood 2: Primrose	Max. 10% of lots 8,000 - 9,000 s.f.	70'	9,000 - 14,000	8'/16'
Neighborhood 3: Sego Lily	N/A	45'	4,500 - 7,000	5'/10'
Neighborhood 4: Sego Lily	Max. 25% of lots 4,500 - 5,000 s.f.	45'	4,500 - 8,000	5'/10'
Neighborhood 5: Daisy	Max. 10% of lots 7,000 - 8,000 s.f.	60'	8,000 - 11,000	6'/12'
Neighborhood 6: Daisy	N/A	50'	4,500 - 7,000	5'/10'
Neighborhood 7: Wild Rose	N/A	45'	5,000 - 7,500	5'/10'

\*In Neighborhood 1: Primrose, lots immediately adjacent to the Pumpkin Patch Neighborhood of Harvest Hills shall be equal to or greater than 10,000 square feet.

\*\* Summary of setbacks. Full setback details can be found on page 26 of Community Plan and in the Development Standards in Section 4 of this Village Plan.






# SECTION 9: Landscape Plan & Plant Palette

## VILLAGE PLAN AREA 1 -- CONCEPT PLANT SCHEDULE

Quantities shown on this sheet are for entire Village Plan Area 1.



- LARGE TREE (2" CALIPER) 364**

Acer platanoides `Emerald Queen`	Emerald Queen Maple
Pinus nigra	Austrian Black Pine
Platanus x acerifolia `Bloodgood`	London Plane Tree
Quercus macrocarpa	Burr Oak
Quercus robur `Fastigiata`	Pyramidal English Oak
Tilia tomentosa	Silver Linden
  
- MEDIUM TREE (2" CALIPER) 853**

Acer negundo `Sensation`	Sensation Box Elder Maple
Gleditsia triacanthos inermis*	Thornless Common Honeylocust*
Tilia cordata	Littleleaf Linden
  
- SMALL TREE (2" CALIPER) 228**

Acer tataricum	Tatarian Maple
Crataegus x lavalleyi	Hawthorn
Malus x `Indian Magic`	Indian Magic Crab Apple
Malus x `Prairifire`	Prairifire Crab Apple
Malus x `Spring Snow`	Spring Snow Crab Apple
Prunus virginiana `Canada Red`	Canada Red Chokecherry

\*Common Honeylocust not to be used in parkstrips or near parking, but may be used within parks or other large open spaces.

Landscape Concept Plan  
Neighborhoods 1 and 2





VILLAGE PLAN AREA 1 -- CONCEPT PLANT SCHEDULE


	<b>LARGE TREE (2" CALIPER)</b> 364	
	Acer platanoides 'Emerald Queen'	Emerald Queen Maple
	Pinus nigra	Austrian Black Pine
	Platanus x acerifolia 'Bloodgood'	London Plane Tree
	Quercus macrocarpa	Burr Oak
	Quercus robur 'Fastigiata'	Pyramidal English Oak
	Tilia tomentosa	Silver Linden
	<b>MEDIUM TREE (2" CALIPER)</b> 853	
	Acer negundo 'Sensation'	Sensation Box Elder Maple
	Gleditsia triacanthos inermis*	Thornless Common Honeylocust*
	Tilia cordata	Littleleaf Linden
	<b>SMALL TREE (2" CALIPER)</b> 228	
	Acer tataricum	Tatarian Maple
	Crataegus x lavallei	Hawthorn
	Malus x 'Indian Magic'	Indian Magic Crab Apple
	Malus x 'Prairifire'	Prairifire Crab Apple
	Malus x 'Spring Snow'	Spring Snow Crab Apple
	Prunus virginiana 'Canada Red'	Canada Red Chokecherry

\*Common Honeylocust not to be used in parkstrips or near parking, but may be used within parks or other large open spaces.





# SECTION 9: Landscape Plan & Plant Palette (cont'd)



## VILLAGE PLAN AREA 1 -- CONCEPT PLANT SCHEDULE

<p>● <b>LARGE TREE (2" CALIPER)</b> 364</p> <p>○ <b>MEDIUM TREE (2" CALIPER)</b> 853</p> <p>○ <b>SMALL TREE (2" CALIPER)</b> 228</p>	<p>Acer platanoides `Emerald Queen` Pinus nigra Platanus x acerifolia `Bloodgood` Quercus macrocarpa Quercus robur `Fastigiata` Tilia tomentosa</p> <p>Acer negundo `Sensation` Gleditsia triacanthos inermis* Tilia cordata</p> <p>Acer tataricum Crataegus x lavalley Malus x `Indian Magic` Malus x `Prairifire` Malus x `Spring Snow` Prunus virginiana `Canada Red`</p>	<p>Emerald Queen Maple Austrian Black Pine London Plane Tree Burr Oak Pyramidal English Oak Silver Linden</p> <p>Sensation Box Elder Maple Thornless Common Honeylocust* Littleleaf Linden</p> <p>Tatarian Maple Hawthorn Indian Magic Crab Apple Prairifire Crab Apple Spring Snow Crab Apple Canada Red Chokecherry</p>
--	--	---

\*Common Honeylocust not to be used in parkstrips or near parking, but may be used within parks or other large open spaces.


<p>■ <b>WILDFLOWER SEED MIX (74,570 sq. ft.)</b> Granite Seed Company: Great Basin Wildflower Mix Apply at 1-2 lbs. per 1,000 sq. ft.</p>	
<p><b>Annuals</b> <i>Centaurea cyanus</i> <i>Cheiranthus allionii</i> <i>Cleome serrulata</i> <i>Coreopsis tinctoria</i> <i>Cosmos sulphureus</i> <i>Eschscholzia californica</i> <i>Gaillardia pulchella</i> <i>Gilia sp.</i> <i>Linaria maroccana</i> <i>Linum grandiflorum</i> <i>Papaver rhoeas</i> <i>Phlox drummondii</i></p>	<p>Bachelor button Wallflower Rocky Mountain Beeplant Plains coreopsis Sulphur cosmos California poppy Firewheel Gilia species Baby snapdragon Scarlet flax Shirley poppy Drummond phlox</p>
<p><b>Perennials</b> <i>Aster sp.</i> <i>Castilleja sp.</i> <i>Coreopsis lanceolata</i> <i>Echinacea purpurea</i> <i>Gaillardia aristata</i> <i>Linum lewisii</i> <i>Lupinus sp.</i> <i>Penstemon sp.</i> <i>Ratibida columnifera</i> <i>Ratibida columnifera forma pulcherrima</i> <i>Rudbeckia hirta</i> <i>Sphaeralcea sp.</i> <i>Balsamorhiza sagittata</i></p>	<p>Aster species Paintbrush species Lance-leaved coreopsis Purple coneflower Blanket flower Lewis blue flax Lupine species Penstemon species Prairie coneflower Mexican hat</p> <p>Black-eyed Susan Globemallow species Arrowleaf balsamroot</p>
<p>Contact:</p>	<p>801-768-4422</p>

■ 4" minus decorative river rock over weed prevention fabric




Landscape Concept Plan  
Neighborhoods 5, 6, and 7






- Planting Mix**  
(size - 1 gallon minimum, grouped in clusters of 3, 5, or 7 per species)
- Perennial Grasses**  
(*Miscanthus sp.*, *Calamagrostis sp.*, *Helictrotrichon sp.*, or *Deschampsia sp.*)
- Perennial Flowers**  
(*Leucanthemum sp.*, *Coreopsis sp.*, *Gaura sp.*, *Geranium sp.*, *Hemerocallis sp.*, *Lavandula sp.*, *Linum sp.*, *Penstemon sp.*, *Rudbeckia sp.*, or *Sedum sp.*)

LANDSCAPE CONCEPT: PRIMARY ENTRANCE SIGN



- Planting Mix**  
(size - 1 gallon minimum, grouped in clusters of 3, 5, or 7 per species)
- Perennial Grasses**  
(*Helictrotrichon sp.* or *Deschampsia sp.*)
- Perennial Flowers**  
(*Leucanthemum sp.*, *Coreopsis sp.*, *Gaura sp.*, *Geranium sp.*, *Hemerocallis sp.*, *Lavandula sp.*, *Linum sp.*, *Penstemon sp.*, *Rudbeckia sp.*, or *Sedum sp.*)

LANDSCAPE CONCEPT: SECONDARY ENTRANCE SIGN (TYPICAL)



- Planting Mix**  
(size - 1 gallon minimum, grouped in clusters of 3, 5, or 7 per species)
- Perennial Grasses**  
(*Helictrotrichon sp.* or *Deschampsia sp.*)
- Annual Flowers**  
(As determined by WDRC)

LANDSCAPE CONCEPT: BUILDER DIRECTIONAL SIGN (TYPICAL)

Landscape Concept Plans  
for Typical Signage



# SECTION 10: Utility Plans

The following maps provide greater detail on the utilities for Wildflower Village Plan Area 1.

Section 10a: Culinary Water Plan

Section 10b: Secondary Water Plan

Section 10c: Sewer Plan

Section 10d: Stormwater Drainage Plan

Section 10e: Master CFP Plan








# SECTION 10b: Secondary Water Plan



WILDFLOWER  
AT SARATOGA SPRINGS



Final design & sizing to be coordinated & approved with final plats.



**DA**  
 1099 W. SOUTH JORDAN PARKWAY  
 SOUTH JORDAN, UT 84095  
 (801) 495-3414





# SECTION 10b (cont'd): Secondary Water Plan

Final design & sizing to be coordinated & approved with final plats.



Secondary Water Pond








# SECTION 10d: Storm Water Drainage Plan


- NOTES**
1. FINAL STORM DRAIN LINE SIZING TO BE DETERMINED WITH FINAL ROADWAY DESIGN.
  2. THESE INFRASTRUCTURE IMPROVEMENTS ARE PRELIMINARY IN NATURE AND SUBJECT TO SECTION 22 OF THE MASTER DEVELOPMENT AGREEMENT.
  3. UDOT HAS ALLOWED THE DEVELOPER TO CO-LOCATE STORAGE WATER AREAS TO SERVE BOTH THE PROJECT AND MVC UPON THE REQUEST AND APPROVAL OF THE CITY.
  4. STORM DRAIN LINES UNDER MVC LAND TO BE INSTALLED BASED ON CURRENT NATURAL GROUND. IT IS ANTICIPATED THAT UDOT WILL LOWER THESE LINES, IF NECESSARY.

**LEGEND**

MOUNTAIN VIEW CORRIDOR	
PROPOSED STORM DRAIN	
STORM DRAIN BASIN CONTRIBUTING AREA	
VILLAGE 1 BOUNDARY	



**WILDFLOWER**  
AT SARATOGA SPRINGS



Final design & sizing to be coordinated & approved with final plats.

An executed agreement between Saratoga Springs & Canal Company allowing for drainage shall be required prior to final plat approval.


If discharge is not allowed into the existing canal to manage the 100-year event, downstream storm facilities will be required according to the City's Capital Facilities Plan and Impact Fee Facilities Plan.

**DAI**  
1099 W. SOUTH JORDAN PARKWAY  
SOUTH JORDAN, UT 84095  
(801) 486-3414





# SECTION 10e: Capital Facility Upgrade Plan



**NOTES**

1. THE IMPROVEMENTS SHOWN ARE IDENTIFIED AS CAPITAL IMPROVEMENTS THROUGH THE SARATOGA SPRINGS CITY IMPACT FEE FACILITY PLANS AND ARE ELIGIBLE FOR IMPACT FEE REIMBURSEMENT AS OUTLINED WITHIN EACH FACILITY / IFPP. OR WILL BE INCLUDED IN A FUTURE IFPP MASTER PLAN.
2. THIS DOCUMENT IS FOR REFERENCE ONLY. THE CITY'S CAPITAL FACILITIES PLAN AND IMPACT FEE FACILITIES PLANS STAND ALONE.



This document is for reference only. The City's Capital Facilities Plans and Impact Fee Facilities Plans stand alone.











# SECTION 11: Vehicular Plan



WILDFLOWER  
AT SARATOGA SPRINGS



- NOTES**
1. TRAFFIC CALMING IS REQUIRED ALONG ALL STREET SEGMENTS LONGER THAN 1000 FEET.
  2. THE INTERSECTION OF HARVEST HILLS BLVD WITH SR68 SHALL BE RECONSTRUCTED TO ADD A DUAL-LEFT-TURN (NORTHBOUND) MOVEMENT IN ACCORDANCE WITH UDOT REQUIREMENTS AND THE WILDFLOWER TRAFFIC STUDY CONTAINED WITHIN THE COMMUNITY PLAN.
  3. MOUNTAIN VIEW CORRIDOR INTERSECTION ARE BASED ON APPROVED UDOT LOCATIONS.



Traffic calming is required along all street segments longer than 1000 feet without at least a 45° bend.

The intersection of Harvest Hills Blvd with SR-68 shall be reconstructed to add a dual-left-turn (northbound) movement in accordance with UDOT requirements if capacity noted in traffic study exceeds phase one and the MVC frontage road has not yet been built. If the frontage road has been constructed, then this requirement is removed.


**DAI**

1099 W. SOUTH JORDAN PARKWAY  
SOUTH JORDAN, UT 84095  
(801) 495-3414





# SECTION 12: Pedestrian & Bicycle Plan



# SECTION 13: Density Transfers

Exhibit Two: Land Use Master Plan (page 14), Equivalent Residential Unit Transfers (page 21), and Density (page 22) of the “Wildflower Community Plan” establish the number of Equivalent Residential Units (ERUs) and density for Wildflower.

An Equivalent Residential Unit (ERU) is defined by the Saratoga Springs Municipal Code as a unit of measurement to evaluate development impacts on public infrastructure including water, sewer, storm drainage, parks, roads and public safety of proposed residential and commercial land uses. Every residential and commercial unit is a minimum of one ERU. Since build-out of the Wildflower development will occur over many years, flexibility is necessary to respond to market conditions, site conditions, and other factors. Therefore, residential density ERUs may be transferred within the project as necessary to improve design, accessibility, and marketability. The City acknowledges that the master developer shall have the ability in its reasonable business judgment to transfer ERUs between residential areas within the project upon written notice to the City and delivery to the City of written consent of the property owners of the neighborhoods which are sending and receiving such densities (if different from the master developer), so long as any such transfer adheres to the following standards:

- » Any transfer of ERUs into or out of any neighborhood type established in the Community Plan shall not exceed fifteen percent (15%) without approval of the City Council. In no case shall the transfer of ERUs into or out of any land use designation or district exceed twenty-five (25%) of that established in the Community Plan. ERU transfers shall comply with the neighborhood breakdown on page 27 of the Community Plan.
- » ERUs may not be transferred from a more intensive neighborhood into a less intensive neighborhood designated in this Community Plan located east of the identified Mountain View Corridor and bordering any portion of the Harvest Hills subdivision if such transfer would result in single family lots smaller than 4,500 square feet.
- » ERUs may not be transferred into any open space or park unless said use and acreage is replaced elsewhere within the same neighborhood.

Village Plan Area 1 is approximately 169 acres in size, and contains 571 units. See Detailed Buildout Allocation in Section 3 for density transfers within Village Plan Area 1.



# SECTION 14: Additional Detailed Plans

The following elements have been included to detail plans and direction contained in the Community Plan for Village Plan Area 1:

Section 14a: Neighborhood Names

Section 14b: Signage Plan

Section 14c: Grading Plan

Section 14d: Open Space Management

Section 14e: Natural Resource Inventory Plan

Section 14f: Wildlife Mitigation

Section 14g: Sensitive Lands Protection


Section 14h: Fire Protection Plan

Section 14i: Traffic Study






# SECTION 14a: Neighborhood Names





# SECTION 14b: Signage Plan




\* Primary Entrance Feature (Development)

\* Secondary Entrance Feature (Development)

\* Secondary Entrance Feature (Neighborhood)

\* Community Directional Temporary Sign







# PRIMARY ENTRANCE FEATURE



CONCEPTUAL DESIGN AND COLOR SCHEME




PLANTER METAL PROFILE  
1" = 1'-0"




TYPICAL ELEVATION


3/8" = 1'-0"




FOOTINGS AND FOUNDATION  
1/4" = 1'-0"



TOP OF MONUMENT BASE  
1/4" = 1'-0"



TOP OF BOX  
1/4" = 1'-0"



ROOF PLAN  
1/4" = 1'-0"

NOTE: Drawings show design intent. Contractor to provide shop drawings for owner/architect to review prior to construction. Contractor to coordinate with owner for finish selections, provide shop drawings for metal panels, and signage lettering. Coordinate with owner for additional information.






# SECONDARY ENTRANCE FEATURE

(Development and Neighborhood)




CONCEPTUAL DESIGN AND COLOR SCHEME


NOTE: Drawings show design intent. Contractor to provide shop drawings for owner/architect to review prior to construction. Contractor to coordinate with owner for finish selections, provide shop drawings for metal panels, and signage lettering. Coordinate with owner for additional information.




FOOTINGS AND FOUNDATION  
1/2" = 1'-0" 1 A102




METAL FLASHING PROFILE  
3/4" = 1'-0" 6 A102




FLOOR PLAN  
1/2" = 1'-0" 2 A102



SOUTH ELEVATION  
1/2" = 1'-0" 5 A102



EAST ELEVATION  
1/2" = 1'-0" 4 A102



ROOF PLAN  
1/2" = 1'-0" 3 A102






# TEMPORARY COMMUNITY DIRECTIONAL SIGN

Maximum Height 12 Feet

There will be up to 16 temporary, fixed way-finding signs in place at any given time. The height may vary depending on the number of builders in a given area. The examples show a directional sign with three and six builders.

All directional signage will be removed when construction is complete and model homes are closed in each neighborhood.

Individual builder directional signs are not allowed within the community.







# SECTION 14c: Grading Plan



WILDFLOWER  
AT SARATOGA SPRINGS



**NOTES**  
1. THE GRADING CONTOURS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. ALL GRADING WILL BE SUBJECT TO THE CITY'S FINAL PLAT ENGINEERING DESIGN ACCEPTANCE PROCESS.

LEGEND	
VILLAGE 1 BOUNDARY	■■■■■■■■
NEIGHBORHOOD BOUNDARY	- - - - -
PROPOSE MAJOR CONTOUR	_____
PROPOSED MINOR CONTOUR	_____



# SECTION 14d: Open Space Management Plan

Wildflower meets the City's requirements for a minimum of 30-percent improved and native, public and private open space within the Planned Community District area, as shown on the following table and maps, and as described below:

UDOT has a total of 26.88 acres of open space within the residential portion of the Wildflower Community Plan. This is located in the Mountain View Corridor, its trails, and the detention basin. (See the Community Level Open Space Exhibit found on page 6 of the Community Plan Amendment.) This accounts for 6.08% open space in the project. The development requires 30%, and developer will contribute to the overall residential area an additional 105.69 acres, which is 23.92% of the total residential land. Wildflower shall be required to meet a 23.92% open space requirement on a phase-by-phase basis to stay compliant, with the remaining percentage coming through UDOT. The remaining 6.08% will be improved by UDOT in conjunction with the Mountain View Corridor.

The amount of open space provided within Village Plan Area 1 is 11.8% of the required total. On the west side of the corridor, an additional 24.62 acres of open space will be dedicated or bonded as part of platting, so that as a cumulative, the plats are always balanced at a minimum of 23.92% open space. Additionally, the developer is committed to spend \$2000/unit on improvements, which is also required to stay balanced on a cumulative basis.





## SECTION 14d: Open Space Management Plan (cont'd)

### Village Plan Area 1

	Units	Acres	Park Construction Value	Total Value Phase	\$2000/Unit Req./Phase	Discrepancy
Neighborhoods 1-7	571	15.73	\$2,071,804	\$2,071,804	\$1,142,000	\$929,804
Additional Open Space Ground Contributed from West of Corridor Towards Village Plan Area 1 Requirement	0	24.62	\$0	\$0	\$0	\$0
<b>Total Village 1</b>	<b>571</b>	<b>40.35</b>	<b>\$0</b>	<b>\$2,071,804</b>	<b>\$1,142,000</b>	<b>\$929,804</b>
Carryover to Village 2	0	0	-\$929,804	\$0	\$0	-\$929,804

### Future Village Plan Requirements

	Units	Acres	Park Construction Value	Total Value Phase	\$2000/Unit Req./Phase	Discrepancy
Future Village Plans	897	65.34	\$864,196	\$864,196	\$1,794,000	-\$929,804
Carryover from Village Plan Area 1	0	0	\$929,804	\$929,804	\$0	\$929,804
<b>Total Future Village Plans</b>	<b>897</b>	<b>71.31</b>	<b>\$1,794,000</b>	<b>\$1,794,000</b>	<b>\$1,794,000</b>	<b>\$0</b>

### UDOT Open Space in MVC Trails & Detention

	Units	Acres	Park Construction Value	Total Value Phase	\$2000/Unit Req./Phase	Discrepancy
UDOT MVC Trails & Detention	0	26.88	\$0	\$0	\$0	\$0
<b>Total UDOT</b>	<b>0</b>	<b>26.0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>

### Total Open Space Required Per Community Plan

	Units	Acres	Park Construction Value	Total Value Phase	\$2000/Unit Req./Phase	Discrepancy
Village Plan Area 1	571	40.35	\$2,071,804	\$2,071,804	\$1,142,000	\$929,804
Future Village Plans	897	65.34	\$864,196	\$864,196	\$1,794,000	-\$929,804
UDOT	0	26.88	\$0	\$0	\$0	\$0
<b>Total Village Plan Area 1</b>	<b>1,468</b>	<b>133</b>	<b>\$2,936,000</b>	<b>\$2,936,000</b>	<b>\$2,936,000</b>	<b>\$0</b>

### Total Open Space Required Per Community Plan

	Units	Acres of Open Space	% of Total Ground
Wildflower Owned (Village Plan Area 1 plus Future Village Plans)	1,468	105.69	23.92%
UDOT	0	26.88	6.08%
<b>Total Village Plan Area 1</b>	<b>1,468</b>	<b>132.57</b>	<b>30%</b>

The open space outside of this Village Plan shall be dedicated at the time any plat does not have the sufficient 23.92% Open Space and sufficient Open Space is not available to dedicate from within this Village Plan.

Estimates for each park and amenity to be prepared and submitted by a licensed landscape architect at time of platting toward the required values of this village plan. Construction values to count all park/open space improvements and equipment costs.







# SECTION 14d: Open Space Management Plan (cont'd)



WILDFLOWER  
AT SARATOGA SPRINGS



Open Space Plan



LEGEND	
LAND USE	
	RESIDENTIAL
	OPEN SPACE & PARKS
	MOUNTAIN VIEW STORM POND
	MOUNTAIN VIEW CORRIDOR
	TRAILS
	UDOT TRAILS
	TRAILS BY OTHERS (TO SHOW CONNECTIVITY)
	VILLAGE 1 BOUNDARY



OPEN SPACE TABULATIONS:	
TOTAL AREA VILLAGE 1:	168.69 ACRES
REQUIRED OPEN SPACE VILLAGE 1 (23.92% SEE OPEN SPACE MASTER PLAN):	40.35 ACRES
PROVIDED OPEN SPACE VILLAGE 1:	15.68 ACRES
(ADDITIONAL 24.67 ACRES TO BE DEDICATED ON WEST SIDE OF MVC AT FINAL)	

\*\*AREA NOT CONTROLLED BY DEVELOPER OPEN SPACE PROVIDED BY UDOT & INCLUDED WITH 6.08% OF OVERALL OPEN SPACE SEE BREAKDOWN:  
**OVERALL OPEN SPACE REQUIRED ALL VILLAGE AREAS (NOT SHOWN): 132.57 ACRES (30.00%)**  
 6.08% OPEN SPACE PROVIDED BY UDOT IN MOUNTAIN VIEW CORRIDOR TRAIL & STORM WATER POND: 26.88 ACRES  
 23.92% OPEN SPACE REQUIRED IN DEVELOPER CONTROLLED GROUND: 105.69 ACRES





Typical Trail Sections



**NOTES**


1. ALL TRAILS SHALL BE ADA ACCESSIBLE AND PROVIDE MAINTENANCE ACCESS.
2. CENTERLINE RADIUS OF MEANDERING TRAILS SHALL BE 100' MIN.





# SECTION 14d: Open Space Management Plan (cont'd)

- Open Space A: Private Neighborhood Park
- Open Space B: Private Neighborhood Park
- Open Space C: Private Greenway
- Open Space D: Public Community Park
- Open Space E: Private Neighborhood Park
- Open Space F: Private Neighborhood Park



Open Space Locator Map






# SECTION 14d: Open Space Management Plan (cont'd)

BUILDER  
DIRECTIONAL SIGN


BENCH


IRRIGATED  
SOD (TYP.)

DECIDUOUS  
TREES (TYP.)



Open Space A Illustrative





Open Space B Illustrative






### WILDFLOWER - OPTION 1 SARATOGA SPRINGS, UTAH OVER ALL SITE PLAN

AREA: 3318 SQUARE FEET  
PERIMETER: 205'  
The information provided is for estimation purposes only.

MEGA TOWER PLAY SYSTEM WITH ADJOINING ARCH AND CLIMBER AND SPINNER.

Play area surfacing to be engineered wood fiber and will conform to the current issue of the "Handbook for Public Playground Safety" published by the Consumer Product Safety Commission (C.P.S.C.) and ASTM F1487-11.



All materials and equipment will conform to the current issue of the "Handbook for Public Playground Safety" published by the Consumer Product Safety Commission (C.P.S.C.) and ASTM F1487-11. The manufacturer will be responsible for correcting any product violations of the C.P.S.C. Guidelines and ASTM F1487-11, to the satisfaction of the Owner, should they be found after installation.

Playground equipment must hold the International Play Equipment Manufacturers Association (IPEMA) certification.

Playground will be accessible in accordance with the latest ADA Accessibility Guidelines (ADAAG) Section 15.6 Play Areas.

Contractor will be responsible for coordinating with the State for a playground safety audit prior to opening playgrounds for use. Final payment will not be authorized until audit is complete and found to be/or is corrected to be in compliance with design standards, recommendations, and requirements.

Playground Safety Audit Certificates for each playground to be provided.

Play Area Capacity: 75-85



<p>To promote safe and proper equipment use by children, Miracle recommends the installation of either a Miracle safety sign or other appropriate safety signage near each playsystem's main entry point(s) to inform parents and supervisors of the age appropriateness of the playsystem and general rules for safe play.</p> <p>AN ENERGY ABSORBING PROTECTIVE SURFACE IS REQUIRED UNDER &amp; AROUND ALL PLAY SYSTEMS.</p>	<b>CD216781</b>		✓	COMPLIES TO CPSC	DESIGNED FOR AGES 5-12 <small>ADDITIONAL GROUND LEVEL ACCESSIBLE ITEMS NEEDED FOR ADA COMPLIANCE</small>	DATE: 1/18/2016	
	GROUND SPACE: 42' X 46' PROTECTIVE AREA: 65' DIA.	✓	COMPLIES TO ASTM	SCALE: 1"=10'-0"			
		✓	COMPLIES TO ADA	TYPE: 0	QUANTITY: 0	CINDI	SHEET 1 of 2

Open Space B Playground Concept







Open Space B Playground Concept





Open Space B Playground Concept






# SECTION 14d: Open Space Management Plan (cont'd)



Open Space C Illustrative





Open Space C Illustrative





# SECTION 14d: Open Space Management Plan (cont'd)




Open Space D Illustrative





# SECTION 14d: Open Space Management Plan (cont'd)

The total capacity for all play equipment shown is approximately 93 children.



All materials and equipment will conform to the current issue of the "Handbook for Public Playground Safety" published by the Consumer Product Safety Commission (C.P.S.C.) and ASTM F1487-11. The manufacturer will be responsible for correcting any product violations of the C.P.S.C. Guidelines and ASTM F1487-11, to the satisfaction of the Owner, should they be found after installation.

Playground equipment must hold the International Play Equipment Manufacturers Association (IPEMA) certification.



Play area surfacing to be engineered wood fiber and will conform to the current issue of the "Handbook for Public Playground Safety" published by the Consumer Product Safety Commission (C.P.S.C.) and ASTM F1487-11.

Playground will be accessible in accordance with the latest ADA Accessibility Guidelines (ADAAG) Section 15.6 Play Areas.

Contractor will be responsible for coordinating with the State for a playground safety audit prior to opening playgrounds for use. Final payment will not be authorized until audit is complete and found to be/or is corrected to be in compliance with design standards, recommendations, and requirements.

Playground Safety Audit Certificates for each playground to be provided.



Open Space D Playground Concept





KOMPAN<sup>®</sup>



DAI WILDFLOWER



Open Space D Playground Concept





**KOMPAN**®




**DAI WILDFLOWER**

Open Space D Playground Concept





SECTION 14d: Open Space Management Plan (cont'd)



Open Space E Illustrative




Open Space F Illustrative





# SECTION 14e: Natural Resources Inventory Plan



### Slopes

Slope greater than 30% = 7.78 Acres. (for purpose of determining sensitive lands area, incidental & isolated area over 30% have not been included.)

### Soils

A Geotechnical Investigation has been conducted for the eastern portion of the Wildflower development by Infinity Consultants, dated January 17, 2014. It is anticipated that the additional parcels within the Wildflower development will have similar soil characteristics. Excerpts from the investigation include:  
•The subsurface soils encountered at the site consist of primarily of sandy clays (CL) and silty clays (CL-ML). Silty sands (SM) and clayey sands (SC) were found interspersed with clayey soils on the ridge and in its near vicinity. Cobbles and boulders are frequently found in the near surface soils and topsoil, layers of gravel are frequently found in the subsurface soils.  
•No subsurface water was encountered to the maximum depth investigated, approximately 16 feet in the test pits and 50 feet in the borings along the northern ridge lines.  
•It is our opinion that the site is suitable for the proposed construction. The buildings supported on shallow spread footings bearing on the undisturbed natural silt or clay soils should be designed for a net allowable pressure of 1,250 pounds per square foot. Shallow footings bearing on natural undisturbed well graded sands, gravels or at least 1 foot of compacted structural fill may be designed for a net allowable bearing pressure of 1,500 psf. Basement footings that are embedded a minimum of 6 feet deep from the native ground surface and are bearing on the undisturbed natural silt or clays may be designed for a net allowable pressure of 1,500 psf. Basement footings embedded more than 6 feet and bearing on undisturbed natural well graded sands or gravels may be designed for a net allowable pressure of 1,800 psf.  
•At the time of the site investigation was conducted, vegetation at the site consisted primarily of sage brush, with farmed and fallow fields, native grasses and weeds were present around the perimeter of the fields.  
•Based on the information collected during our field investigation and subsequent laboratory testing, we anticipate that collapse-susceptible soils will not be encountered during construction.  
•No active faults are mapped to extend through or near the property. The closest mapped fault to the site lies beneath Utah Lake, located approximately 4.5 miles to the south. (Machette, 1992).

The full Geotechnical Investigation is to be submitted separately and available for further detail.

### Wetlands

No wetlands exist on this site.

### Special Protection Areas

A Phase I Environmental Site Assessment has been conducted for the Wildflower development by Infinity Consultants, dated December 12, 2013. The conclusion of this assessment states:  
The Subject Property consists of open, unused land with no structures. There has not been any historic use of the property that is inconsistent with its current use. There is no evidence of current or past use, storage, or production of hazardous chemicals or petroleum products at environmentally significant levels on the Subject Property.

In the opinion of Infinity Consultants, this assessment has provided no evidence of "recognized environmental conditions," as defined by the ASTM standard, in connection with the Subject Property. Therefore, it can be concluded that no further action is required.

The full Phase I Environment Site Assessment is to be submitted separately and available for further detail.

### Dams and Canals

No dams exist above this site. The Provo Reservoir Canal clips the far northeast and southeast corners of the property.

### Shrubs, Trees and Wildlife

Shrub and tree stands are outlined per recent aerial photos. Wildlife is typical of the foothill areas of the Wasatch Front. No known endangered, threatened or rare flora or fauna are known to exist on the site. Any trees greater than 2 1/2" caliper removed during grading operations will be replaced within the development with like kind.

### Flood Plain Data

All project area is within flood zone "X" as shown on FIRM maps 4955170105B (July 17, 2002) and 4955170115B (July 17, 2002)

### Mitigation Requirement

If areas of proposed development are determined unsuitable due to any of the above conditions, acceptable mitigation must be completed prior to development, i.e. soil stabilization, environmental hazards, etc.



Natural Resources Inventory Plan

Legend	
	Stands of Trees
	Existing Gravel Road
	Existing Drainage Channel
	Existing Canal

Existing Sensitive Land Calculations	
Sensitive area calculation:	7.78 Acres
(for purpose of determining sensitive lands area, incidental & isolated area over 30% have not been included.)	

----- Village Area 1 Boundary (added to this map for reference purposes)

This Natural Resources Inventory Plan was approved as part of the Wildflower Community Plan, and is used for reference in several of the following sections.



# SECTION 14f: Wildlife Mitigation Plan

As indicated in the Natural Resources Inventory Plan in Section 14e of this document, Wildlife is typical of the foothill areas of the Wasatch Front, and no known endangered, threatened, or rare flora or fauna are known to exist on the site. Therefore, no wildlife mitigation is required for Village Plan Area 1.



# SECTION 14g: Sensitive Lands Protection

Sensitive lands cannot be included within lots. However, in accordance with the mass grading plan approved with the Community Plan, areas that are graded out of sensitive lands are allowed to be included within lots. As indicated in the Natural Resources Inventory Plan in Section 14e of this document, there are several areas of sensitive lands (shown in red) within the Village Plan Area 1 boundary. These areas represent land with slopes greater than 30%, and are primarily found in neighborhoods #1 and #2 Primrose, with a small amount found in the open space south of neighborhood #7 Wild Rose. These areas are anticipated to have slopes less than 30% after the mass grade is complete. Areas with slopes greater than 30% that remain outside of the defined building pads after mass grading of the area will be protected by means of Slope Easements. These sensitive lands shall be required to have a note placed on the plat to identify the location of the easement and the lots affected.


## **Example of Slope Easement on Plat**

Special note for lots xxx – xxx: All homes and accessory buildings or structures shall be constructed only within the buildable area for such lots and outside the slope easement area identified on this plat. No changes in grade shall be permitted within the slope easement area without express written permission from the City. This prohibition shall not apply to the planting of grass, flowers and small shrubs and trees indigenous to the area, or placement of decorative rock and similar non-invasive landscaping. This exception for planting does not permit the installation of irrigation systems within the slope easement which shall require the express written permission from the City.



# SECTION 14h: Fire Protection Plan

As described in the Wildflower Community Plan, The project lies entirely within the City defined Wildland/Urban Interface. At the time a preliminary plat is submitted, a Fire Protection Plan in accordance with the Utah Wildland-Urban Interface Code shall be prepared to assess site specific wildfire risk. This assessment includes consideration of location, topography, aspect, flammable vegetation, climatic conditions and fire history. The plan shall address water supply, access, building ignition and fire-resistance factors, fire protection systems and equipment, defensible space and vegetation management. Feasibility of the Fire Protection Plan will be reviewed at time of preliminary plat and shall be in accordance with the Utah Wildland Urban Interface Code.



# SECTION 14i: Traffic Study

The revised traffic study addresses the entire Wildflower community. However, it is broken into two segments. The first is the number of units that can be developed and have an adequate capacity on current collectors. The second segment is the number of units that can be developed and have an adequate capacity on the MVC frontage roads are built.



# SECTION 14i: Traffic Study (cont'd)

**HALES ENGINEERING**  
innovative transportation solutions

## **Wildflower** Traffic Impact Study



# WILDFLOWER

AT SARATOGA SPRINGS

**Saratoga Springs, Utah**  
September 2016

UT16-841

1220 North 500 West, Ste. 202 Lehi, UT 84043 p 801.766.4343  
www.halesengineering.com



# SECTION 14i: Traffic Study (cont'd)



## EXECUTIVE SUMMARY

This study addresses the traffic impacts associated with proposed Wildflower residential development in Saratoga Springs, Utah. The proposed development is located on the west side of Redwood Road (SR-68) and the existing Harvest Hills residential development.

Included within the analyses for this study are the traffic operations and recommended mitigation measures for existing conditions and plus project conditions (conditions after development of the proposed project) at key intersections and roadways in the vicinity of the site. Future 2020 and 2040 conditions are also analyzed.

### TRAFFIC ANALYSIS

The following is an outline of the traffic analysis performed by Hales Engineering for the traffic conditions of this project.

#### Existing (2016) Background Conditions Analysis

Hales Engineering performed weekday morning (7:00 – 9:00 a.m.) and afternoon (4:00 to 6:00 p.m.) peak period traffic counts at the following intersections:

- Redwood Road (SR-68) / 2100 North (SR-85)
- Redwood Road (SR-68) / Spring Hills Drive
- Redwood Road (SR-68) / Harvest Hills Boulevard
- Providence Drive / Harvest Hills Boulevard
- Harvest Moon Drive / Spring Hills Drive
- Providence Drive / Harvest Moon Drive

These counts were performed on Wednesday, January 27, 2016. The a.m. peak hour was determined to be between the hours of 7:00 and 8:00 a.m. and the p.m. peak between 5:00 and 6:00 p.m. The afternoon volumes were approximately 17 percent higher than the morning volumes and were used for this analysis. Detailed count data are included in Appendix A.

As shown in Table ES-1, the Redwood Road (SR-68) / Spring Hills Drive intersection is currently operating at LOS F. All other study intersections are currently operating at acceptable levels of service during the p.m. peak hour. The 95<sup>th</sup> percentile queues at the Redwood Road (SR-68) / Harvest Hills Boulevard extend for several hundred feet on the north- and southbound approaches. The southbound queue, at times, blocks an upstream intersection. The queues on the eastbound approach to the Redwood Road (SR-68) / Spring Hills Drive intersection also extend for several hundred feet. No other significant queueing was observed during the p.m. peak hour.



# SECTION 14i: Traffic Study (cont'd)



## **Project Conditions Analysis**

The proposed land use for the development has been identified as follows:

- Single-Family Detached Housing: 1,069 Dwelling Units
- Residential Condominium/Townhouse: 246 Dwelling Units

The development was split into two phases for the analysis. Phase I included everything east of the Mountain View Corridor. Phase II included everything west of Mountain View Corridor. The total trip generation for Phase I of the development is as follows:

- Daily Trips: 5,184
- a.m. Peak Hour Trips: 408
- p.m. Peak Hour Trips: 502

The total trip generation for Phase II of the development is as follows:

- Daily Trips: 6,042
- a.m. Peak Hour Trips: 471
- p.m. Peak Hour Trips: 577

## **Existing (2015) Plus Project Conditions Analysis**

As shown in Table ES-1, all three study intersections on Redwood Road (SR-68) are anticipated to operate at LOS F with project traffic added during the p.m. peak hour. All other study intersections are anticipated to operate at LOS A. The 95<sup>th</sup> percentile queues on all three approaches to the Redwood Road (SR-68) / Harvest Hills Boulevard intersection are anticipated to extend for several hundred feet.

## **Future (2020) Background Conditions Analysis**

As shown in Table ES-1, the Redwood Road (SR-68) / 2100 North (SR-85) and Redwood Road (SR-68) / Spring Hills Drive intersection are anticipated to operate at LOS F with future 2020 traffic conditions. All other study intersections are anticipated to operate at acceptable levels of service during the p.m. peak hour. The 95<sup>th</sup> percentile queues at the Redwood Road (SR-68) / 2100 North (SR-85) intersection are anticipated to be excessive on all three approaches during the p.m. peak hour. The 95<sup>th</sup> percentile queues on the southbound approach to the Redwood Road (SR-68) / Harvest Hills Boulevard intersection are anticipated to extend several hundred feet. The queues on the eastbound approach to the Redwood Road (SR-68) / Spring Hills Drive intersection are anticipated to be excessive due to the difficulty of executing left-turn movements at this location.



# SECTION 14i: Traffic Study (cont'd)



## **Future (2020) Plus Project Conditions Analysis**

As shown in Table ES-1, the Redwood Road (SR-68) / 2100 North (SR-85) intersection is anticipated to operate at LOS F with project traffic added. All other study intersections are anticipated to operate at acceptable levels of service during the p.m. peak hours. Significant queuing is anticipated at the Redwood Road (SR-68) / 2100 North (SR-85) intersection on all approaches. No other significant queuing is anticipated.

## **Future (2040) Plus Project Conditions Analysis**

As shown in Table ES-1, the Redwood Road (SR-68) / 2100 North (SR-85) intersection is anticipated to operate at LOS F, and the Southbound Mountain View Corridor Frontage Road / Harvest Hills Boulevard intersection is anticipated to operate at LOS E during the p.m. peak hour. All other study intersections are anticipated to operate at acceptable levels of service. Significant queuing is anticipated at the Redwood Road (SR-68) / 2100 North (SR-85) on the southbound approach, and at the Southbound Mountain View Corridor Frontage Road / Harvest Hills Boulevard intersection on the south- and eastbound approaches.



# SECTION 14i: Traffic Study (cont'd)



**TABLE ES-1  
P.M. Peak Hour  
Saratoga Springs - Wildflower TIS**

Intersection	Existing 2016 Background	Existing 2016 Plus Project	Future 2020 Background	Future 2020 Plus Project	Future 2040 Plus Project
Description	LOS (Sec/Veh <sup>1</sup> )				
Redwood Road (SR-68) / 2100 North (SR-85)	-	-	F (>80)	F (>80)	F (>80)
Redwood Road (SR-68) / New Access Road	-	F (>50) / EB	-	C (18.6) / EB	C (18.8) / EB
Redwood Road (SR-68) / Spring Hills Drive	F (>50) / EB	F (>50) / EB	F (>50) / EB	D (26.0) / EB	C (22.2) / EB
Redwood Road (SR-68) / Harvest Hills Boulevard	D (51.7)	F (>80)	C (25.5)	B (14.3)	C (30.0)
Providence Drive / Harvest Hills Boulevard	A (2.4)	A (3.4)	A (3.0)	A (3.4)	A (6.1)
Harvest Moon Drive / Spring Hills Drive	A (7.5) / WB	A (5.6) / NB	C (15.7) / SB	A (3.4) / WB	A (3.8) / WB
Providence Drive / Harvest Moon Drive	A (2.0)	A (2.4)	A (2.1)	A (2.1)	A (2.3)
SB MVC / 2100 North (SR-85)	-	-	-	B (14.7)	-
NB MVC / 2100 North (SR-85)	-	-	-	C (23.3)	-
SB MVC / 1500 North	-	-	-	C (23.5)	C (20.9)
NB MVC / 1500 North	-	-	-	B (13.3)	A (9.8)
SB MVC / Harvest Moon Drive	-	-	-	C (21.0)	B (15.7)
NB MVC / Harvest Moon Drive	-	-	-	B (18.4)	B (13.1)
SB MVC / Harvest Hills Boulevard	-	-	-	D (49.6)	E (77.1)
NB MVC / Harvest Hills Boulevard	-	-	-	C (30.2)	C (34.7)

1. Intersection LOS and delay (seconds/vehicle) values represent the overall intersection average for roundabout, signalized, all-way stop controlled intersections and the worst approach for all other unsignalized intersections.  
 2. This intersection is a project access and was only analyzed in "plus project" scenarios.  
 3. This intersection was eliminated as part of the proposed project and was only analyzed in "background" scenarios.  
 Source: Hales Engineering, February 2016



# SECTION 14i: Traffic Study (cont'd)



## RECOMMENDATIONS

The following mitigation measures are recommended:

### **Existing (2016) Background Conditions Analysis**

The Redwood Road (SR-68) / Spring Hills Drive intersection is a stop-controlled access onto a major highway. It is generally expected that there will be delays at these types of intersections, especially during peak traffic periods. The Redwood Road (SR-68) / Harvest Hills Boulevard intersection is currently meeting UDOT criteria for dual left-turn lanes on the northbound approach. Although this intersection is currently operating at an acceptable LOS, it is recommended that dual left-turn lanes be constructed at this location.

### **Existing (2016) Plus Project Conditions Analysis**

As previously discussed, the Redwood Road (SR-68) / Harvest Hills Boulevard intersection is currently meeting UDOT criteria for dual left-turn lanes on the northbound approach. It is recommended that dual left-turn lanes be constructed at this location.

### **Future (2020) Background Conditions Analysis**

Additional capacity will be required to accommodate the projected traffic on Redwood Road (SR-68). It is recommended that Redwood Road (SR-68) be expanded to a seven-lane cross section. It is recommended that the Redwood Road (SR-68) / Spring Hills Drive intersection be converted to a right-in right-out (RIRO) configuration, as it is anticipated that executing left-turn movements will continue to be difficult. It is likely that drivers will elect to utilize Harvest Hills Boulevard as an alternate access.

### **Future (2020) Plus Project Conditions Analysis**

The Redwood Road (SR-68) / 2100 North (SR-85) intersection is a junction of two major roadways. Future plans are for 2100 North (SR-85) to become a freeway connecting I-15 to the Mountain View Corridor, and for the Mountain View Corridor to take the place of Redwood Road (SR-68) as primary north/south route through the western part of the county. When these projects are completed, east/west traffic will be grade separated and the amount of north/south traffic will be diverted to the Mountain View Corridor. Until these projects are completed, it is recommended that an innovative intersection design be implemented to accommodate the large amounts of traffic at this intersection. No other mitigation measures are recommended.



# SECTION 14i: Traffic Study (cont'd)



## **Future (2040) Plus Project Conditions Analysis**

It is anticipated that there will be a high number of right-turning vehicles on the southbound approach to the Mountain View Corridor Frontage Road / Harvest Hills Boulevard intersection. It is recommended that right-turning capacity be increased at this location with the addition of a free right-turn lane onto westbound Harvest Hills Boulevard. No other mitigation measures are recommended.

## **SUMMARY OF KEY FINDINGS/RECOMMENDATIONS**

The following is a summary of key findings and recommendations:

- It was assumed that the proposed project would be built in two phases: the first phase on the east side of the Mountain View Corridor right-of-way, and second on the west side. Trips generated by Phase I of the project were included in the existing (2015) background and plus project analyses. Trips from both Phase I and Phase II were included in all future (2020 and 2040) analyses.
- It was assumed for these analyses that the Mountain View Corridor frontage roads would be constructed through the project area for the future (2020 and 2040) plus project scenarios, and that the Mountain View Corridor and 2100 North freeways would be constructed for the future (2040) plus project scenario.
- The Redwood Road (SR-68) / 2100 North (SR-85) intersection is anticipated to operate at LOS F in 2020 and 2040. It is recommended that an innovative intersection design be implemented at this location.
- The Redwood Road (SR-68) / Harvest Hills Boulevard intersection currently meets UDOT criteria for dual left-turn lanes on the northbound approach. It is recommended that these turn lanes be constructed.
- It is anticipated that the Redwood Road (SR-68) / Harvest Hills Boulevard intersection will operate at LOS E with Phase I project traffic added. With only 90% of the planned 567 single-family homes completed, the intersection will operate at LOS D.
- The Redwood Road (SR-68) / Spring Hills Drive intersection is anticipated to continue to operate at LOS F through 2020. This is generally expected at stop-controlled intersections on busy roadways.
- It is anticipated that a large portion of traffic on Redwood Road (SR-68) will reroute to the new Mountain View Corridor system, alleviating some of the congestion along the corridor.
- All intersections along the Mountain View Corridor frontage roads are anticipated to operate at acceptable levels of service, with the exception of the Southbound Mountain View Corridor Frontage Road / Harvest Hills Boulevard intersection in 2040. There are a high number of right-turning vehicles anticipated on the southbound approach to this intersection. It is recommended that a free right-turn lane be constructed on this approach.



# SECTION 14i: Traffic Study (cont'd)



- All existing intersections within the existing Harvest Hills residential development currently operate at acceptable levels of service, and are anticipated to continue as such through 2040 with traffic from the proposed project added.



# SECTION 15: Site Characteristics

General site characteristics for Wildflower were provided in the Community Plan, page 92, first paragraph in the geotechnical investigation (text is provided below).

Wildflower is a proposed 800-acre development “located west of Redwood Road approximately 1.5 miles north of highway 73 (Lehi Main Street/Cedar Fort Road) in Saratoga Springs Utah. The project area is located on the northern and western borders of the Harvest Hills subdivision and consists of a northern region and a southern region that are joined by a narrow neck of property. The northern regional slopes generally to the east and has some steep slopes. The southern region of the property predominantly slopes to the southeast with mild slopes. Approximately 70 percent of the property was previously farmed. The remaining 30 percent of the property is undisturbed rangeland with wild grasses and sagebrush.”

General site characteristics were also provided in the Community Plan on page 89, under the summary of the Environmental Site Assessment conducted by Infinity Consultants.

- » “Surficial soils were visually inspected and appear to be sandy silts with gravel and boulders at higher elevations. The property is covered by native grasses, weeds, and plowed fields,.
- » The property slopes gradually and changes several hundred feet from its high point in the northwest to the lowest points in the northeast and south. The slope is much steeper in the northwest, in the vicinity to the western most City water tank.
- » An irrigation canal runs through the Subject Property at two locations, First in the southern part of the property just north of and then crossing Cedar Fort Road, then second in the northeast portion of the property.
- » All drainages crossing the property seem to end at the irrigation canal.
- » There are high power electrical transmission lines bordering the west boundary of the Subject Property.
- » There are no constructed structures on the entire property or evidence of past structures.”



# SECTION 16: Findings

Village Plan Area 1 is the 169-acre first phase within the 800-acre Wildflower Community Plan located in Saratoga Spring, Utah. The Wildflower Village Plan Area 1 is compliant with all PC Zone Requirements for Village Plans as defined in section 19.26.09 of the Saratoga Springs Municipal Code. We find that Village Plan Area 1:

- a. is consistent with the adopted Wildflower Community Plan;
  - » Village Plan Area 1 adheres to the development standards, thoroughfare types, and open spaces types and requirements established in the Wildflower Community Plan.
- b. does not exceed the total number of Equivalent Residential Units (ERUs) dictated in the adopted Community Plan;
  - » The number of potential ERUs established in the Community Plan for Village Plan Area 1 is 580. Village Plan Area 1 establishes a maximum of 571 within the seven neighborhoods that comprise Village Plan Area 1.
- c. for an individual neighborhood, does not exceed the total number of ERUs established in the adopted Wildflower Community Plan;
  - » The ERUs were reduced from 109 to 95 to increase the size of the neighborhood park located in Neighborhood 4.
- d. is consistent with the utility, infrastructure, and circulation plans of the Wildflower Community Plan; includes adequately sized utilities, services, and roadway networks to meet demands; and mitigates the fair-share of off-site impacts;
  - » Village Plan Area 1 implements the utility, infrastructure, and circulation plans as specified in the Wildflower Community Plan.
- e. properly integrates utility, infrastructure, open spaces, pedestrian and bicycle systems, and amenities with adjacent properties;
  - » Wildflower has been designed to accommodate significant infrastructure elements that are important to the City within the structure of the property. Wildflower was designed to maximize pedestrian, bike, and other mobility options. Open space is highly integrated to provide direct and easy access to residents.
- f. contains the required elements as required in section 19.26.10 of the Saratoga Springs Municipal Code.



# SECTION 17: Mitigation Plans

According to the Natural Resources Inventory Plan in Section 14e:

- » Slopes greater than 30% total 7.78 acres for the entire Wildflower property;
- » No wetlands exist on this site;
- » No subsurface water was encountered to the maximum depth investigated;
- » The site is suitable for the proposed construction;
- » No active faults are mapped to extend near or through the property;
- » There is no evidence of current or past use, storage, or production of hazardous chemicals or petroleum products at environmentally significant levels on the Subject Property;
- » No dams exist above this site;
- » The Provo Reservoir Canal clips the far northeast and southeast corners of the property;
- » No known endangered, threatened or rare flora or fauna are known to exist on the site; and
- » All project area is within the flood zone "X."

Section 14e states that "if areas of proposed development are determined unsuitable due to any of the above conditions, acceptable mitigation must be completed prior to development, i.e. soil stabilization, environmental hazards, etc."

As described in Section 14g: Sensitive Lands Protection, there are several small areas of sensitive lands with slopes over 30%. The lots in Village Plan Area 1 have been laid out to ensure that the sensitive lands in these areas remain in the undeveloped rear yards. These sensitive lands will be protected from disturbance during the development process through the establishment of construction limit lines. As described in Section 14e: Natural Resources Inventory Plan, "any trees greater than 2 1/2" caliper removed during grading operations will be replaced within the development with like kind or better, 2 1/2" caliper minimum."





Wildflower Village 1 Offsite Estimates					
Saratoga Springs, UT					
Engineer's Construction Cost Estimate Per Master Development Plan Exhibits					
Project Costs					Notes
Item	Est. Quantity	Unit	Unit Price	Total Amount	
<b>Sanitary Sewer - Offsite</b>					
12" PVC Main	3,365	lf	\$ 40.00	\$ 134,600	
18" PVC Main	488	lf	\$ 50.00	\$ 24,400	
48" Manholes	13	ea	\$ 2,500.00	\$ 32,500	
T-Patch Repair in Ex. Asphalt	50	lf	\$ 16.00	\$ 800	
Bore Under Canal & Redwood Road	200	lf.	\$ 350.00	\$ 70,000	
Traffic Control on Redwood Road	1,064	lf	\$ 20.00	\$ 21,280	
Canal Crossing Repair	1	ls	\$ 25,000.00	\$ 25,000	
Imported Pipe Bedding	1,002	tons	\$ 12.00	\$ 12,021	
Imported Trench Backfill	5,009	tons	\$ 8.00	\$ 40,071	
Subtotal Sanitary Sewer - Offsite				\$ 360,673	
<b>Culinary Water - Offsite</b>					
12" PVC	2,739	lf	\$ 40.00	\$ 109,560	
8" PVC	1,072	lf	\$ 28.00	\$ 30,016	
Imported Pipe Bedding	579	tons	\$ 12.00	\$ 6,946	
Imported Trench Backfill	991	tons	\$ 8.00	\$ 7,927	
Subtotal Culinary Water - Offsite				\$ 154,448	
<b>SUBTOTAL</b>				\$ 515,121	
<b>TOTAL CONSTRUCTION COST</b>				\$ 515,121	
<b>NOTES:</b>			<b>DISCLAIMER</b>		
1. Estimates are only for OFFSITE utility improvements relative to Village 1 of the Wildflower Development.			THE DATA AND INFORMATION PRESENTED HEREIN HAVE BEEN PRODUCED CONSISTENT WITH INDUSTRY STANDARDS BY OPERATORS EXERCISING REASONABLE SKILL AND CARE. THIS DATA AND INFORMATION IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO GUARANTEE OR WARRANTY EXPRESSED OR IMPLIED IS MADE WITH RESPECT TO THE ACCURACY OF THIS DATA OR INFORMATION. IN NO EVENT WILL LEI CONSULTING ENGINEERS AND SURVEYORS INC. BE LIABLE FOR ANY LOSS OF PROFIT OR ANY OTHER COMMERCIAL DAMAGE INCLUDING BUT NOT LIMITED TO SPECIAL, INCIDENTAL, CONSEQUENTIAL, OR OTHER DAMAGES RESULTING FROM THE USE OF THIS INFORMATION OR DATA.		
2. Refer to the Master Development Plan Exhibits for the location of all offsite improvements.					



# SECTION 19: Master Development Agreement

A Master Development Agreement has been approved by the City and was recorded with the County on February 24, 2015.

